

A)	Op. W/S Scheme Depur.	Cleaning of UGSR/OHSR by First retaining 75mm water in the tank & Cleaning the tank with the mixture of Sodium Hypochlorite/bleaching powder, thereafter spraying on roof and walls of tank mixture of bleaching Powder. Sodium hypochlorite & rinsing after 60 minutes. Disinfect the tank and filling and scouring the tank to ensure proper quality of water.	As per Actual	@Rs.42900/-
1	Op. W/S Scheme Depur			
		(i) Cleaning of 1 No. UGSR (Capacity 230000 ltr) as per Department Specification and all other works contingent there too.		
2	Op. W/S Scheme Damowal Chandoli			
		(i) Cleaning of 1 No. UGSR (Capacity 50000 ltr) as per Department Specification and all other works contingent there too.		
3		Painting and Writing at UGSR for Writing information of capacity dia and date of cleaning		
B)	Op. W/S Scheme Fatehpur, Dohar Bhera			
		Cleaning of UGSR/OHSR by First retaining 75mm water in the tank & Cleaning the tank with the mixture of Sodium Hypochlorite/bleaching powder, thereafter spraying on roof and walls of tank mixture of bleaching Powder. Sodium hypochlorite & rinsing after 60 minutes. Disinfect the tank and filling and scouring the tank to ensure proper quality of water.	As per Actual	@Rs.42900/-
1	Op. W/S Scheme Fatehpur			
		(i) Cleaning of 1 No. UGSR (Capacity 130000 ltr) as per Department Specification and all other works contingent there too.		
2	Op. W/S Scheme Dohar Bhera			
		(i) Cleaning of 1 No. UGSR (Capacity 136000 ltr) as per Department Specification and all other works contingent there too.		
3		Painting and Writing at UGSR for Writing information of capacity dia and date of cleaning		
C)	Op. W/S Scheme Beh Fatto, Beh Ranga			
		Cleaning of UGSR/OHSR by First retaining 75mm water in the tank & Cleaning the tank with the mixture of Sodium Hypochlorite/bleaching powder, thereafter spraying on roof and walls of tank mixture of bleaching Powder. Sodium hypochlorite & rinsing after 60 minutes. Disinfect the tank and filling and scouring the tank to ensure proper quality of water.	As per Actual	@Rs.40500/-
1	Op. W/S Scheme Beh Fatto			
		(i) Cleaning of 1 No. UGSR (Capacity 150000 ltr) as per Department Specification and all other works contingent there too.		
2	Op. W/S Scheme Beh Ranga			
		(i) Cleaning of 1 No. UGSR (Capacity 100000 ltr) as per Department Specification and all other works contingent there too.		
3		Painting and Writing at UGSR for Writing information of capacity dia and date of cleaning		
D)	Providing Public Health services in Meritorious Children 10+2 school at Talwara Distt Hsp.			
		Providing Laying jointing fixing testing of ISI Marked GI Pipe of 20 mm I/d & 50 mm I/d including excavation and P/F Brass valves 20 mm I/d & Gun Metal Peat valve 50 mm I/d complete in all respect in Meritorious school block Talwara Distt Hosharpur.	As per Actual	@Rs.49500/-
E)	Op. W/S Scheme Depur			
		P/F Peat valve of 50 mm I/d including jointing testing nut bolts etc and removal of leakage of 2", 3" M.S./GI Pipe at various places complete in all respects.	As per Actual	@Rs.20000/-
F)	Op. W/S Scheme Jugal Sunebra			
		Earthwork in excavation in removing leakage/blockage of 3", 2" MS/GI/GI Pipeline including cost of bailing out water	As per Actual	@Rs.18000/-

W/S Scheme: Beh Ranga			
	Earthwork in excavation in removing leakage /blockage of 80mm i/d, 50 mm i/d, 40 mm i/d MS/GI/CI Pipeline including cost of bailing out water and welding complete in all respect.	As per Actual	@Rs.25000/-
H)	Op. W/S Scheme Beh Jogan		
	Earthwork in excavation in removing leakage /blockage of 150mm i/d, 80mm i/d, 50 mm i/d, 40 mm i/d MS/GI/CI Pipeline including cost of bailing out water and welding complete in all respect.	As per Actual	@Rs.25000/-
I)	Providing Public Health services in Meritorious Children 10+2 school at Talwara Distt Hsp.		
	Desalting of man hole including all safety measure & disposal of silt at appropriate place in meritorious school Talwara.	As per Actual	@Rs.40000/-
H)	Op. W/S Scheme Heer Beh		
	Earthwork in excavation in removing leakage /blockage of 80mm i/d, 50 mm i/d, 40 mm i/d MS/GI/CI Pipeline including cost of bailing out water and welding complete in all respect.	As per Actual	@Rs.22000/-
H)	Op. W/S Scheme Jugal Sunehra		
	P/F 80 mm i/d Pipeline and sluice valve of class PN1.6 & NRV of Size 80 mm i/d for Making Connection of New T/Well with Collecting Tank. Including cost of welding excavation, dismantling etc complete in all respect at W/S Scheme Jugal Sunehra.	As per Actual	@Rs.49500/-

Note:- The details of work can be seen in the office of the undersigned on any working day.

Conditions:-

1. Sales tax/inter state sales tax or any other chargeable duty must be specially mentioned separately, a failing which no such tax or duty will be allowed at subsequent Stage.
2. The undersigned reserves the right to reject any or all the tenders received without assignment any reason.
3. The undersigned has the liberty to increase or decrease the quantity of the material.
4. Conditional/Telegraphic quotation shall be rejected.
5. The rates should be quoted for destination.
6. The quotation received after the due date shall be rejected.
7. In case due date happens to be holidays/declared holiday then quotation will be opened on next working day at the same time.
8. If the contract is terminated before the completion of a work the payment will be made accordingly.
9. Experienced candidates will be preferred.
10. Work should be done as per P.W.D Specifications.
11. Contractor should Visit the water Supply Scheme before filling the tender there after Taking estimate filling quotation accordingly.


Sub Divisional Engineer,
W/S & Sanitation Sub Division No.1,
Talwara.

Enclt No. 48-52 dt. 10-01-2025

Copy of above is forwarded to the following for information & Necessary action.

1. Executive Engineer W/S & Sanitation Division Talwara.
2. Sub Divisional Engineer W/S & Sanitation SD No. 2 Talwara, SD No. 1/2 Mukerian.
3. Notice Board for All Contractors and others.


Sub Divisional Engineer,
W/S & Sanitation Sub Division No.1,
Talwara