

## QUOTATION NOTICE

Quotation for the following material/work are invited in Sealed envelope from the authorized dealer/reputed suppliers/ enlistment contractors so as to reach office of the undersigned on **27/3/20 at 03:00 PM.** The quotations will be opened in the presence of the suppliers or authorized Agents who may like to be present. **Estimated Amount: 352436/-**

Sr. No.	Name the Works	Category/ Qty.	Amount	Due date of opening the Quotations
1	A/Mtc. of PHS provided in 46 No. PB Minister and Senior Officer residence, Sector-39, Chandigarh (work done at Kothi No. 922, Sector-39, Installation of Monoblock Motor & G.I. Pipe work)			
1 28.35	Providing ,laying, jointing, fixing and testing ISI Marked G.I. Pipe (as per IS 1239) B Class including cost of specials (such as tees, bends, sockets, elbows etc.) ,painting with anti corrosive bitumastic paint, testing, cutting, threading Inside building complete (b) 20mm i/d	39.80 Mtr.		
2 28.4	Providing, fixing and jointing G.I Union Couplings(of approved make with the approval EIC) as per IS 1879 in G.I. Pipe lines complete in all respect. a) 20mm i/d G.I. Union	3 No.		
3 28.56	Cutting holes upto 23cm square through B.B. in cement walls or stone masonry wall in cement for pipes, and making good the same & finishing according to existing finish where required.			
	Through wall 22.86 cm thick	3.00 No.		
4	Construction of Platform for Monoblock motor including cost of matrial and labour complete job.	1 Job		
5	P/F 1.00 BHP electrical Monoblock Motor Pump Cormption make complete in all respects.	1 No.		
6	P/F MS Angel Iron Shed for monoblock motor with Fibre Sheet including cost of matrial and labour complete in all respects.	1 No.		
7	P/F PVC Floor Trap of Size 3" complete in all respects.	2 No.		
8	P/F PVC Tee of Size 3" complete in all respects.	1 No.		
9	P/F PVC Socket of Size 3" complete in all respects.	2 No.		
10 30.74 III	Providing and fixing in position singel socket SWR UPVC soil waste or antisiphonage pipes as per IS 13592 of E.D.C manufacture or of any other reputed firm including cutting, jointing, wastage, but excluding cost of jointing.			
	B Single Socket Type B			
	B 110mm o/d SWR UPVC Pipe line laid complete	2.00 Mtr.		
	C 90mm o/d SWE UPVC Pipe line laid complete	4.30 Mtr.		
11 30.77 C	Providing PVC solvent cement joints to SWR Pipes and specials including cost of PVC solvent cement and tools etc of approved make (to the approval of Engineer-in-charge )			
	b 110mm o/d	2 No.		
	90mm o/d	10 No.		
12	P/F PVC reducer of Size 6"x4" complete in all respects.	1		
13 30.99	Providing and fixing in position gully traps fixed in cement concrete 1:4:8 complete with Grating 150mm x 150mm, cover and frame clear opening 300mm x 300mm and out of side size 330mm x 330mm and chamber including cost of all bricks work in cement mortar 1:5 cement concrete 1:2:4 in coping around cover and frame etc. as per standard design minimum depth of water should be 150 mm with a minimum seal 50mm.			
	a)100mm internal Diametre S.W.gully trap with H.C.I. grating and cast iron cover weighing approximately 7.26 kg. and frame clear opening 300mm x 300mm and out of side size 330mm x 330mm	1 No.		
14 29.72	Making connection of newly laid sewer in walls of existing manhole of fully charge sewer including cost of plugging sewer, desilting, removal of sullage water and making good of khudda	1 No.		
15 29.4	Excavation of trenches in a Streets, Lanes or in Open Area for Storm Sewers and Manholes to Full Depths as Shown in Drawings,excluding Shoring, Timbering of Poling Board Frame System Type, dressing to correct			

To be  
quoted by  
the  
contracto  
r

	sections and dewatering, provision for diversion for traffic, protection of existing services i.e. telephone cables ,electric lines, water supply lines and gas lines.night signals, profiles, Pegs, Sight rails, boning rods, crossing over trenches for access to the houses, watching, fencing etc., fixing and maintenance of caution boards, refilling trenches, watering of refill in 15 cm layers, ramming and restoration of surface to original conditions and removal of Surplus Spoil from the Site of Works, for all Works other than connections to Ventilating Shafts upto a Lead of 15 mtr		
	i) All classes of soil except rocky	5.83 Cum	
16 10.13	Cement concrete 1:2:4		
	(a) with stone ballast or shingle		
	i) Mixing by manual means	0.57 cum	
2	<b>A/Mtc. of PHS provided in 46 No. PB Minister and Senior Officer residence, Sector-39, Chandigarh (work done at Kothi No. 922, Sector-39, Installation of PVC Water Storage Tank)</b>		
1	Construction of Platform for placing PVC Water Storage Tank with Brickwork and Plaster etc. including cost of Material and labour complete.	1 No.	
2 30.97A	Providing & placing in position on terrace (at all floor levels) HDPE water storage tanks of approved make (to the approval of Engineer -in-charge) with cover with suitable locking arrangement and making necessary holes for inlet, outlet and over flo pipes but without fittings and base support for tank.		
	(i) Triple Layer Tanks	2000 Ltr.	
3 30.96 B	P/f in Position automatic brass Cock in Tanks. ii 20mm i/d	1 No.	
4 28.43	Providing, fixing and jointing ISI Marked Gun-Metal peet valves (Heavy Pattern) as per IS 778 with hand wheels, on G.I. Pipe lines laid in the ground or inside buildings including all carriages complete. b 20mm i/d Gun Metal Peet Valve heavy pattern.	2 No.	
5 30.98	Providing and fixing in position G.I. Tank Nipple of approved make (to the approval of Engineer-in-charge) in PVC Water storage tanks complete in all respect.		
	b G.I. Tank Nipple 20mm i/d	2 No.	
6 28.45	Making connection with the existing G.I. branch main up to 40mm size pipe including cutting of existing pipe line, threading of pipe lines from both ends and fixing of G.I Tee etc.in the pipe line.		
7	Deep Cleaning of Bathroom with the help of surf etc. including cost of matrial and labour complete job.	2 No.	
8	Refurbishing of Bathroom including grouting and touching of tiles including cost of material and labour complete job.	2 No.	
9	Raising of Manhole Covers including dismantling, brick work, plaster etc. including cost of material and labour complete job.	1 Job	
10	Carriage of malba from site of work to dumping ground complete job.	1 Job.	
3	<b>A/Mtc. of Providing Electrical Equipment in PB Civil Sectt-2, Sector-9, Chanidgarh.</b>		
1	Fixing and Installation of 2.0TR Split A.C.	3 Nos.	
2	Gas Charging in Split type A.C. 1.0 and 2.0 TR Capacity	5 Nos.	
4	<b>Annual Maintenance of Aquaguar Water Purifiers (07 Nos. UV Water Purifiers 07 No. RO) system installed at Minister Complex, Sector 39, Chandigarh for the Period of 01.04.2023 to 29.02.2024 and all other works contingent thereto.</b>	07 No. UV 07 No. RO	
5	<b>Annual Maintenance of Aquaguar Water Purifiers (07 Nos. UV Water Purifiers 07 No. RO) system installed at Minister Complex, Sector 39, Chandigarh for the Period of 01.04.2023 to 29.02.2024 and all other works contingent thereto.</b>	07 No. UV 07 No. RO	
6	<b>Annual Maintenance of Aquaguar Water Purifiers (10 Nos. UV Water Purifiers 03 No. RO) system installed at Minister Complex, Sector 39, Chandigarh for the Period of 01.04.2023 to 29.02.2024 and all other works contingent thereto.</b>	10 No. UV 03 No. RO	
7	<b>Annual Maintenance of Aquaguar Water Purifiers (11 Nos. UV Water Purifiers) system installed PB Civil Sectt-2, Sector 9, Chandigarh for the Period of 01.04.2023 to 29.02.2024 and all other works contingent</b>	20 No. UV	

	thereto		
8	Annual Maintenance of Aquaguar Water Purifiers (07 Nos. UV Water Purifiers 06 No. RO) system installed PB Raj Bahwan, Sector-6, Chandigarh for the Period of 01.04.2023 to 29.02.2024 and all other works contingent thereto.	07 No. UV 06 No. RO	

### CONDITIONS

1. Sale Tax, GST or any other chargeable duty must be specially mentioned, failing which no such tax or duty will be allowed at subsequent stage.
2. The undersigned reserve the right to accept or reject any or all the tenders without assigning any reasons.
3. Conditional/telegraphic quotation shall be rejected.
4. The rates should be quoted for destination.
5. The quotations received after the due date shall be rejected.
6. In case the due date is declared a holiday, the tender will be opened on the next working day.

  
 Sub Divisional Engineer,  
 Water Supply & Sanitation Sub Division No.1,  
 at Chandigarh

Endst No. 636-645

Dated: 21-3-2023

A Copy of the above is forwarded to Executive Engineer W/S & Sanitation Divn. No.1, at Chandigarh/ Sub Divisional Engineer, W/S & Sanitation Sub Division No. 2/3, Mohali, all Contractors & Notice Board for information and necessary action.

  
 Sub Divisional Engineer,  
 Water Supply & Sanitation Sub Division No.1,  
 at Chandigarh