

ਕੁਟੇਸ਼ਨ/ਟੈਂਡਰ ਨੋਟਿਸ

ਮਿਤੀ. 02.05.2023

ਇਸ ਦਫ਼ਤਰ ਵੱਲੋਂ ਇਸ ਮਹਿਕਮੇ ਦੇ ਪ੍ਰਮਾਣਿਤ ਠੇਕੇਦਾਰਾਂ ਪਾਸੋਂ ਲਮਸਮ ਦੇ ਅਧਾਰ 'ਤੇ ਹੇਠ ਦਰਸਾਏ ਕੰਮਾਂ ਨੂੰ ਕਰਵਾਉਣ ਲਈ ਕੁਟੇਸ਼ਨਾਂ ਆਨਲਾਈਨ ਮੰਗੀਆਂ ਜਾਂਦੀਆਂ ਹਨ। ਕੁਟੇਸ਼ਨਾਂ ਮਿੱਥੇ ਸਮੇਂ ਅਤੇ ਮਿਤੀ ਅਨੁਸਾਰ ਇਸ ਦਫ਼ਤਰ ਵਿਖੇ ਪਹੁੰਚਣੀਆਂ ਚਾਹੀਦੀਆਂ ਹਨ।

Operation & Maintenance of Judicial Court Complex, Govt. Residence Buildings, DAC Gurdaspur.

ਅਨੁਮਾਨਤ ਲਾਗਤ :- 49999/-

ਲੜੀ ਨੰ	ਕੰਮ ਦਾ ਵੇਰਵਾ	ਮਾਤਰਾ	ਰੇਟ
1	P/F Brass made Float Valve	As per Site	Per Unit Rate should be quoted by Agency/Contractor
2	P/F PVC Connection pipe 900mm long		
3	Providing, laying, Fixing, jointing, cutting & testing of uPVC Pipes & Specials (6 kg./cm ²) complete in all respects as per ISI-4985 standard analysis. Size 90mm o/d 6kg/cm ²		
4	P/F PVC Connection pipe 600mm long		
5	P/F 15mm i/d Swan Neck Tap,		
6	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes as per IS 15778 (ISI marked with the prior approval of Engineer-in-Charge), having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing including jointing of pipes & fittings with one step PVC solvent cement and testing of pipes complete as per direction of Engineer-in-Charge. SDR 11 CPVC pipes & fittings 20mm o/d		
7	P/F 15mm i/d Angle Valve		
8	P/F 15mm i/d Angle Valve 2 in one		
9	P/F 15mm i/d Short Body Bib Cock		
10	P/F CP Brass Soap Dish		
11	Providing & fixing of CI grating Jali 6"x6"		
12	P/F of FTA Brass 20mmx20mm		
13	P/F of MTA Brass 20mmx20mm		
14	P/F CPVC Ball Valve 25mm		
15	P/F 15mm i/d Angle Valve		
16	P/F 15mm i/d Shower Head Size 6"x6"		
17	P/F 15mm i/d Shower Arm 1'-6" Long		
18	P/F PTMT Ball cock 15mm		
19	P/F CP Brass Towel Ring		
20	P/F Waste pipe 4'		
21	P/F Brass Made Concealed Disc of 15mm Heavy duty		
22	P/F Taps Body		
23	P/F 15mm i/d Garden Tap (Nozzle)		
24	Removing of leakages including cost of excavation of soil bailing out water stringing jointing cutting and cost of CI D-Joint, pipes and specials complete in all respect 90mm i/d		
25	Providing of double legged Aluminum Ladder size 6' long		

ਖੋਲਣ ਦਾ ਸਮਾਂ :- ਇਹ ਕੁਟੇਸ਼ਨ ਦਸਤੀ ਤੌਰ 'ਤੇ ਮਿਤੀ. 04.05.2023 ਨੂੰ ਸਮਾਂ ਸਵੇਰੇ 10:30 ਵਜੇ ਤੱਕ ਲਈਆਂ ਜਾਣਗੀਆਂ ਅਤੇ ਦੁਪਹਿਰ 12:30 ਵਜੇ ਸੰਬੰਧਤ ਠੇਕੇਦਾਰ ਜਾਂ ਉਹਨਾਂ ਦੇ ਨੁਮਾਇੰਦਿਆਂ ਦੀ ਹਾਜ਼ਰੀ ਵਿੱਚ ਖੋਲੀਆਂ ਜਾਣਗੀਆਂ।

ਸ਼ਰਤਾਂ :-

1. ਇਹ ਕੰਮ ਵਿਭਾਗ ਦੀਆਂ ਸਪੈਸਿਫਿਕੇਸ਼ਨਾਂ ਅਨੁਸਾਰ ਮੁਕੰਮਲ ਕਰਨਾ ਹੋਵੇਗਾ।
2. ਨਿਮਨਹਸਤਾਖ਼ਰ ਨੂੰ ਅਧਿਕਾਰ ਹੋਣਗੇ ਕਿ ਉਹ ਇਹ ਕੁਟੇਸ਼ਨਾਂ ਕਿਸੇ ਵੀ ਪੱਧਰ 'ਤੇ ਬਿਨਾਂ ਕਿਸੇ ਕਾਰਨ ਦੱਸੇ ਰੱਦ ਕਰ ਸਕਦੇ ਹਨ।
3. ਸ਼ਰਤਾਂ ਵਾਲੀਆਂ ਜਾਂ ਈ-ਮੇਲ ਰਾਹੀਂ ਪ੍ਰਾਪਤ ਹੋਈਆਂ ਕੁਟੇਸ਼ਨਾਂ ਸਵੀਕਾਰ ਨਹੀਂ ਕੀਤੀਆਂ ਜਾਣਗੀਆਂ।
4. ਉਕਤ ਮਿਕਦਾਰ ਆਰਜ਼ੀ ਤੌਰ 'ਤੇ ਲਈਆਂ ਗਈਆਂ ਹਨ, ਠੇਕੇਦਾਰ ਨੂੰ ਅਸਲ ਹੋਏ ਕੰਮ ਦੇ ਅਨੁਸਾਰ ਅਦਾਇਗੀ ਕੀਤੀ ਜਾਵੇਗੀ।

Sohi
ਉਪ ਮੰਡਲ ਇੰਜੀਨੀਅਰ,
ਜ/ਸ ਅਤੇ ਸੈਨੀਟੇਸ਼ਨ ਉਪ ਮੰਡਲ ਨੰ:1,
ਗੁਰਦਾਸਪੁਰ।

ਪਿੱਠ ਅੰਕਣ ਨੰ: 873-82 ਮਿਤੀ. 02/5/2023

ਉਪਰੋਕਤ ਦੀ ਨਕਲ ਹੇਠ ਲਿਖੇ ਅਨੁਸਾਰ ਸੂਚਨਾਂ ਅਤੇ ਅਗਲੇਰੀ ਯੋਗ ਕਾਰਵਾਈ ਹਿੱਤ ਭੇਜੀ ਜਾਂਦੀ ਹੈ ਜੀ :-

1. ਕਾਰਜਕਾਰੀ ਇੰਜੀਨੀਅਰ ਜਲ ਸਪਲਾਈ ਅਤੇ ਸੈਨੀਟੇਸ਼ਨ ਮੰਡਲ ਨੰ:1/2 ਗੁਰਦਾਸਪੁਰ।
2. ਉਪ ਮੰਡਲ ਇੰਜੀਨੀਅਰ ਜਲ ਸਪਲਾਈ ਅਤੇ ਸੈਨੀਟੇਸ਼ਨ ਉਪ ਮੰਡਲ ਧਾਰੀਵਾਲ/ਕਲਾਨੌਰ/ਕਾਹਨੂੰਵਾਨ/ਦੋਰਾਂਗਲਾ/ਦੀਨਾਨਗਰ।
3. ਲੇਬਰ ਅਤੇ ਕੋਆਪਰੇਟਿਵ ਸੁਸਾਇਟੀ।
4. ਸਾਰੇ ਠੇਕੇਦਾਰ।
5. ਨੋਟਿਸ ਬੋਰਡ।

Sohi
ਉਪ ਮੰਡਲ ਇੰਜੀਨੀਅਰ,
ਜ/ਸ ਅਤੇ ਸੈਨੀਟੇਸ਼ਨ ਉਪ ਮੰਡਲ ਨੰ:1,
ਗੁਰਦਾਸਪੁਰ।