

## ਕੁਟੇਸ਼ਨ/ਟੈਂਡਰ ਨੋਟਿਸ

ਮਿਤੀ. 02.05.2023

ਇਸ ਦਫ਼ਤਰ ਵੱਲੋਂ ਇਸ ਮਹਿਕਮੇ ਦੇ ਪ੍ਰਮਾਣਿਤ ਠੇਕੇਦਾਰਾਂ ਪਾਸੋਂ ਲਾਮਸਮ ਦੇ ਅਧਾਰ 'ਤੇ ਹੇਠ ਦਰਸਾਏ ਕੰਮਾਂ ਨੂੰ ਕਰਵਾਉਣ ਲਈ ਕੁਟੇਸ਼ਨਾਂ ਆਨਲਾਈਨ ਮੰਗੀਆਂ ਜਾਂਦੀਆਂ ਹਨ। ਕੁਟੇਸ਼ਨਾਂ ਮਿੱਥੇ ਸਮੇਂ ਅਤੇ ਮਿਤੀ ਅਨੁਸਾਰ ਇਸ ਦਫ਼ਤਰ ਵਿਖੇ ਪਹੁੰਚਣੀਆਂ ਚਾਹੀਦੀਆਂ ਹਨ।

**Operation & Maintenance of Judicial Court Complex, Govt. Residence Buildings, DAC Gurdaspur.**

ਅਨੁਮਾਨਤ ਲਾਗਤ :- 49999/-

ਲੜੀ ਨੰ	ਕੰਮ ਦਾ ਵੇਰਵਾ	ਮਾਤਰ	ਰੇਟ
1	P/F PVC Connection pipe 900mm long	As per Site	Per Unit Rate should be quoted by Agency/Contractor
2	P/F PVC Connection pipe 600mm long		
3	P/F 15mm i/d short body Bib Cock		
4	P/F Waste pipe 4'		
5	Providing, laying, Fixing, jointing, cutting & testing of uPVC Pipes & Specials (6 kg/cm <sup>2</sup> ) complete in all respects as per ISI-4985 standard analysis. Size 90mm o/d 6kg/cm <sup>2</sup>		
6	P/F Brass made Float Valve		
7	Repair of Cover of Road Gully Chamber in car parking under basement with Cement Concrete		
8	P/F 15mm i/d Angle Valve		
9	P/F 15mm i/d Swan Neck Tap		
10	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes as per IS 15778 (ISI marked with the prior approval of Engineer-in-Charge), having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing including jointing of pipes & fittings with one step PVC solvent cement and testing of pipes complete as per direction of Engineer-in-Charge. SDR 11 CPVC pipes & fittings 20mm o/d		
11	P/F 15mm i/d Pillar Cock With Foam Flow Complete.		
12	Providing and fixing in position Chinaware European type water closet P trap or S trap of approved make (to the approval of the Engineer-in-charge) consisting of 10 ltr. PVC flushing cistern ISI marked, PVC short bend 32 mm dia including cost of seat cover complete in all respect and to the entire satisfaction of Engineer-in-charge. Size 57.5x34.5x39cm		
13	Providing and fixing in position vitreous chinaware white lavatory suites of approved make (to the approval of Engineer-in-charge) including Rack Bolt Screw Pair 115mm long without CP fittings complete in all respect. Size 550 mm x 400 mm x 815 mm		
14	P/F upvc Pipe 110 mm 6kg/cm <sup>2</sup>		
15	Providing & fixing upvc Elbow 4"		
16	Providing & fixing upvc Socket 4"		
17	Providing & fixing upvc TEE 4"x4"		
18	Removing of leakages including cost of excavation of soil bailing out water stringing jointing cutting and cost of CI D-Joint, pipes and specials complete in all respect 90mm i/d		
19	P/F 15mm i/d Garden Tap (Nozzle)		
20	P/F of FTA Brass 20mmx20mm		
21	P/F of MTA Brass 20mmx20mm		
22	P/F CPVC Ball Valve 25mm		
23	P/F CPVC Ball Valve 20mm		
24	P/F CPVC Union 20mm		
25	Providing & fixing of Over Head Shower with Square Arm 450mm long		
26	Providing & fixing of Hand Shower with 3 flow HS & 1.5m flexible tube with hook		

**ਖੋਲਣ ਦਾ ਸਮਾਂ :-** ਇਹ ਕੁਟੇਸ਼ਨ ਦਸਤੀ ਤੌਰ 'ਤੇ ਮਿਤੀ. 04.05.2023 ਨੂੰ ਸਮਾਂ ਸਵੇਰੇ 10:30 ਵਜੇ ਤੱਕ ਲਈਆਂ ਜਾਣਗੀਆਂ ਅਤੇ ਦੁਪਹਿਰ 12:30 ਵਜੇ ਸੰਬੰਧਤ ਠੇਕੇਦਾਰ ਜਾਂ ਉਹਨਾਂ ਦੇ ਨੁਮਾਇੰਦਿਆਂ ਦੀ ਹਾਜ਼ਰੀ ਵਿੱਚ ਖੋਲੀਆਂ ਜਾਣਗੀਆਂ।

**ਸ਼ਰਤਾਂ :-** 1. ਇਹ ਕੰਮ ਵਿਭਾਗ ਦੀਆਂ ਸਪੈਸਿਫਿਕੇਸ਼ਨਾਂ ਅਨੁਸਾਰ ਮੁਕੰਮਲ ਕਰਨਾ ਹੋਵੇਗਾ।

2. ਨਿਮਨਹਸਤਾਖਰ ਨੂੰ ਅਧਿਕਾਰ ਹੋਣਗੇ ਕਿ ਉਹ ਇਹ ਕੁਟੇਸ਼ਨਾਂ ਕਿਸੇ ਵੀ ਪੱਧਰ 'ਤੇ ਬਿਨਾਂ ਕਿਸੇ ਕਾਰਨ ਦੱਸੇ ਰੱਦ ਕਰ ਸਕਦੇ ਹਨ।

3. ਸ਼ਰਤਾਂ ਵਾਲੀਆਂ ਜਾਂ ਈ-ਮੇਲ ਰਾਹੀਂ ਪ੍ਰਾਪਤ ਹੋਈਆਂ ਕੁਟੇਸ਼ਨਾਂ ਸਵੀਕਾਰ ਨਹੀਂ ਕੀਤੀਆਂ ਜਾਣਗੀਆਂ।

4. ਉਕਤ ਮਿਕਦਾਰ ਆਰਜ਼ੀ ਤੌਰ 'ਤੇ ਲਈਆਂ ਗਈਆਂ ਹਨ, ਠੇਕੇਦਾਰ ਨੂੰ ਅਸਲ ਹੋਏ ਕੰਮ ਦੇ ਅਨੁਸਾਰ ਅਦਾਇਗੀ ਕੀਤੀ ਜਾਵੇਗੀ।

Sohi  
ਉਪ ਮੰਡਲ ਇੰਜੀਨੀਅਰ,  
ਜ/ਸ ਅਤੇ ਸੈਨੀਟੇਸ਼ਨ ਉਪ ਮੰਡਲ ਨੰ:1,  
ਗੁਰਦਾਸਪੁਰ।

ਪਿੱਠ ਅੰਕਣ ਨੰ: 913-22 ਮਿਤੀ. 02/5/2023

ਉਪਰੋਕਤ ਦੀ ਨਕਲ ਹੇਠ ਲਿਖੇ ਅਨੁਸਾਰ ਸੂਚਨਾਂ ਅਤੇ ਅਗਲੇਰੀ ਯੋਗ ਕਾਰਵਾਈ ਹਿੱਤ ਭੇਜੀ ਜਾਂਦੀ ਹੈ ਜੀ :-

- ਕਾਰਜਕਾਰੀ ਇੰਜੀਨੀਅਰ ਜਲ ਸਪਲਾਈ ਅਤੇ ਸੈਨੀਟੇਸ਼ਨ ਮੰਡਲ ਨੰ:1/2 ਗੁਰਦਾਸਪੁਰ।
- ਉਪ ਮੰਡਲ ਇੰਜੀਨੀਅਰ ਜਲ ਸਪਲਾਈ ਅਤੇ ਸੈਨੀਟੇਸ਼ਨ ਉਪ ਮੰਡਲ ਧਾਰੀਵਾਲ/ਕਲਾਨੌਰ/ਕਾਹਨੂੰਵਾਨ/ਦੌਰਾਂਗਲਾ/ਦੀਨਾਨਗਰ।
- ਲੇਬਰ ਅਤੇ ਕੋਆਪਰੇਟਿਵ ਸੁਸਾਇਟੀ।
- ਸਾਰੇ ਠੇਕੇਦਾਰ।
- ਨੋਟਿਸ ਬੋਰਡ।

Sohi  
ਉਪ ਮੰਡਲ ਇੰਜੀਨੀਅਰ,  
ਜ/ਸ ਅਤੇ ਸੈਨੀਟੇਸ਼ਨ ਉਪ ਮੰਡਲ ਨੰ:1